#### Burlington Tunnel Emergency Repairs: A Case History

by: K. Pidgeon - ECI Rail Constructors, Inc. M. Boscardin - Boscardin Consulting Engineers, Inc. W. Riehl, III – Rail America, Inc.

> RETC - 21 June 2011 San Francisco

#### **Presentation Organization**

- Project Introduction
- Ground Conditions
- Original Tunnel Construction
- 2008 Rehabilitation
- The Emergency Repairs
- Lining Response/Performance
- Summary and Conclusions



#### **Project Background**

340 ft Long, Horseshoe-Shaped with Curved Walls
4º Horizontal Curve, 60 ft of Overburden
Inside Dimensions - 17 ft High by 16 ft Wide
Constructed by Vermont Central RR 1860 - 1861
Brick Lining Supported on Limestone Block Footings
Limestone Cobble Floor
Owned by New England Central Railroad (Rail America)



Vermont Interactive Map Viewer Vermont Center for Geographic Information (VCGI)

#### **Burlington Tunnel**



# 4 Degree Horizontal Curve



# **Ground Conditions**

- On the Shores of Lake Champlain
- Tunnel Through a 100-ft-High Sand Ridge
- Fine to Medium Sand
- Wind Blown Sand from Glacial Marine Deltaic Deposits
- Running Sand Conditions Below Ground Water
- Some Varved Clay Encountered During Repairs
- Ground Water Level Below Invert

# Loose Fine-Medium Sand



#### **Original Tunnel Construction**

- Construction Started 1 November 1860
- Construction Completed 17 May 1861
- Ground Reported to be "Quick Sand"
- Vertical Wooden Shield with Top Heading and Bench Excavation, Forepoling
- Initial Lining Contiguous 12-in. x 12-in. Timbers, Backpacking with Cordwood, Timber Invert Struts
- Excavated Dimensions 25 ft High by 22 ft Wide

#### Original Tunnel Construction, Con't.

- Used 700,000 Board ft of Lumber
- 2-ft-Thick Brick Masonry Final Lining
- Concrete Fill Between Masonry Timber Linings
- Construction 24/7 85 Men in Two Shifts
- Average Tunneling Rate 3 ft per day
- Portals
  - Headwalls 39 ft High Limestone Masonry 6 ft thick at Bottom
  - Wing Walls 18 ft Thick at Bottom, 4 ft Thick at Top

# Sketch of Initial Lining

Excavation 18.7 cy/ft Over Excavation 1.3 cy/ft Concrete Packing 1.35 cy/ft Cordwood Packing 35 cy/ft Timber Lining 838.2 Board ft/ft



### Tunnel Lining Condition at 148 Yrs Old





# 2008 Pre-Rehab Condition

#### 2008 Pre-Rehab Condition



#### 2008 Pre-Rehab Condition



#### 2008 Pre-Rehab Condition



#### 2008 Rehabilitation Plan

#### Original Intent of 2008 Rehab

- Mitigate Lining Distress Due to Weathering, Seepage, Freeze-Thaw, Age and Impacts
- Apply 6-inch Shotcrete Internal Lining, with Weep Holes
- Lower Tracks to Compensate for Shotcrete

#### Pre-2008 Rehab Included:

 Shotcrete, Bolting, Pointing, Insertion of Masonry

#### **Emergency Condition**

**Developed Rapidly After Floor Removal** 

Tunnel Sidewalls Moved Inward

Additional Cracking Observed

Immediate Response - Stabilize and Assess

# Wall Movement



#### Cracking Caused by Rehab Construction



## 15 Sept – Emergency Concrete Bracing



# **Emergency Bracing Slab**



Technical Approach to Repairs and Emergency Response

Immediately Stabilize Wall Movements Monitor Further Wall Movements Investigate Causes of Movements Evaluate Lining Loads, Stresses, Cracking Design Permanent Invert Struts Complete Emergency and Original Rehab Monitor During and Following Construction

# Lining Coring



### **Crack and Survey Monitoring**





## Shotcrete Work

# Cross Section of Rigid Track System Capacity = 28.5k/ft



## Invert Slab Replacement



# Completed Base Slab



Rigid Track Structure Before Concrete

## Test Car



# **Concreting New Track Structure**



# **Grouting Cracks**



#### 2008 Timeline of Events

- 15 Sept Install Emergency Invert Brace, ECI Engaged
- 15-22 Sept Assess Tunnel, Core Lining, Install Monitoring
- 20 Sept Mill up to 18" off Emergency Concrete Brace
- Mid Sept Mid Oct Shotcrete Work
- 14-27 Oct Replace Emergency Brace Slab in Segments
- Late Oct Install 18-ft-Long Approach Slab at Each Portal
- 27 Oct 3 Nov Construct Rigid Track System
- 3 Nov Run Test Car for Clearance Check
- 6 Nov Install Concrete for Rigid Track
- 10 Nov Pass Test Train
- 10-13 Nov Finalize Alignment and Surfacing, Turn Over to RR
- 14-21 Nov Install Grout Tubes and Grout Cracks

# Summary and Conclusion

- Emergency Repair & Rehab Work Completed in 2 Months
- Rapid Response to the Emergency Condition Allowed Completion of the Originally Planned Repairs Close to the Original Schedule
- Flexible, Coordinated and Innovative Construction Approaches Contributed to Success
- Construction of the Original Repair Scheme May Have Been Possible with Low Pressure, Low Vibration Equipment, But Long-Term Performance of the Tunnel May Have Been Compromised without a Permanent Invert Strut.

# Nov 2010 Inspection



# Crack Monitor Nov 2010

- Wall Convergence 0 to ¼ inch Since November 2008
- Typically 1/8 inch Convergence
- Approximately Equal Estimated Shrinkage of Invert Struts
- No New Cracking or Widening of Cracks Observed



# **Questions?**

J.

1